

## Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet
	<p>Discontinued line at this Cor., on account of Umatilla Indian Reservation.</p> <p>Land; high &amp; mountainous, sloping W.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack.</p> <p>Dense undergrowth of pine, fir &amp; tamarack.</p>	
	N. bet. Secs. 7 & 8.	
	Var. 20° E.	
15.62	Dry gulch, course 150 ft. below Sec. Cor.	
17.60	Indian Trail, brs. E. & W.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on N. face, 175 ft. above dry gulch, from which,</p> <p>A fir, 7 ins. diam., brs. N. 35° E., 12 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A fir, 18 ins. diam., brs. S. 55° E., 12 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
44.00	Descend hill, brs. N.W. & S.E.	
60.25	Small dry ravine, course N.E., 200 ft. below $\frac{1}{4}$ Sec. Cor. and ascend.	
73.50	Enter glade, brs. N.E. & S.W.	
77.50	Top of hill, brs. N.E. & S.W. and enter timber, brs. N.E. & S.W., 150 ft. above last ravine.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 5, 6, 7, &amp; 8, marked</p> <p>T.2 S., R.35 E., S.5 on N.E.</p> <p>T.2 S., R.35 E., S.6 on N.W.</p> <p>S 7 on S.W. and</p> <p>S.8 on S.E. faces, with</p> <p>5 notches on S. and</p> <p>5 notches on E. edges, from which,</p> <p>A fir, 12 ins. diam., brs. N. 33° E., 16 lks. dist., marked T.2 S., R.35 E., S.5, B.T.</p> <p>A fir, 18 ins. diam., brs. N. 17° W., 40 lks. dist., marked T.2 S., R.35 E., S.6, B.T.</p>	