

Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains		Feet
	N. on true line bet. Secs. 5 & 6.	
		Var. 17°30'E.
2.00	Enter glade, brs. N.W. & S.E.	
3.00	Descend hill, brs. N.W. & S.E.	
5.50	Leave glade & enter timber, brs. N.W. & S.E.	
36.50	Enter meadow, brs. E. & W., 400 ft. below point of descending hill.	
37.00	Leave meadow, brs. E. & W.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., 25 ft. above meadow, marked $\frac{1}{4}$ S. on W. face, from which,	
	A fir, 5 ins. diam., brs. N.30°W., 20 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	A fir, 10 ins. diam., brs. S.64°E., 13 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	Discontinued line at this Cor. in this Tp., so as not to encroach upon the Umatilla Indian Reservation, and as N. Bdy. of Tp. was discontinued at the $\frac{1}{4}$ Sec. Cor., bet. Secs. 4 & 33, there is no line to close to.	
	Land; mountainous.	
	Soil; 2nd rate.	
	Heavily timbered with fir, spruce, tamarack & pine, 36.50 chs.	
	Dense undergrowth of fir, tamarack, pine & mountain laurel.	
		Sept. 29, 1882.
<hr/> General Description. <hr/>		
	The land in this Tp. is high & mountainous and generally heavily timbered with fir, pine, tamarack & spruce of good quality and valuable, and dense undergrowth of same.	
	The soil on Big & Little Meadows is 1st rate, remainder of Tp., 2nd & 3rd rate.	
	Several claims have been taken in the N. portion of Tp., one on Big Meadow in Sec. 10 & one in Sec. 2. The Baker City branch of O.R. & N. Co.'s railroad crosses N.E. Cor. of Tp.	