

Resurvey Subdivisional Lines, T.2 S., R.35 E., W. M.

Chains	Feet
	<p>Timber is yellow pine, balsam and lodgepole pine.</p> <p>The altitude ranges from 4500 ft. to 5500 ft. and snow lies on the ground a great part of the year.</p> <p>Natural bunch grass affords good pasture and hardy grains and grasses are grown.</p> <p>No settlers live in this fraction, but settlers on adjacent lands expect to claim some of the lands.</p> <p style="text-align: right;">Oct.27, 1917.</p> <p style="text-align: right;"><u>L.E.Wilkes</u> U.S. Surveyor.</p>
<p>Resurvey Portion Subdivisional Lines, T.2 S., R.35 E., W. M. As surveyed by same Surveyor; Under Contract No. 38, Dated Apr. 18, 1917.</p>	
	<p>From the Cor. to Secs. 17, 18, 19 & 20, W. retracing bet. Secs. 18 & 19; at 40.00 chs. no trace of $\frac{1}{4}$ Sec. Cor., and at 76.85 chs. intersect the W. Bdy. of Tp., 517 lks. N. of Cor. to Secs. 13, 18, 19 & 24, previously described.</p> <p>Thence</p> <p>N.89°09' E., resurveying line bet. Secs. 18 & 19.</p> <p>Along S. edge of canyon, through heavy timber and medium undergrowth.</p>
38.39	<p>Apportioned distance.</p> <p>Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked,</p> <p style="text-align: center;"> $\frac{1}{4}$ $\frac{S18}{S19}$ 1917 </p> <p>from which,</p> <p style="padding-left: 40px;">A lodgepole pine, 6 ins. diam., brs. S.30°W., 6 lks. dist. marked $\frac{1}{4}$ S., B.T.</p> <p style="padding-left: 40px;">A lodgepole pine, 6 ins. diam., brs. N.60°E., 7 lks. dist. marked $\frac{1}{4}$ S., B.T.</p> <p>Descend 18 ft. to</p>
39.61	Dry gulch, course N.W.; ascend 130 ft. to
48.60	Top of ascent, brs. N.W. & S.E.; over rolling bench land.
76.75	Road, brs. N.W. & S.E.
77.02	Intersect Cor. of Secs. 17, 18, 19 & 20, which is an old post, 4 ins. sq., firmly set, marked & witnessed as described by the Surveyor-General, except that all bearing