

Retracement & Survey Portion Subdivisions, T.2 S., R.35 E., W.M.

Chains	Feet
<p>Timber; fir, pine & balsam. Undergrowth; willow, balsam & pine.</p>	
<p>The Cor. to Secs. 4, 5, 8 & 9 is an old post, lying loose on the ground, marked & witnessed as described by the Surveyor General, except that the S.W. & N.W. bearing trees are now dead, I perpetuate this Cor., as follows: at the exact Cor. point</p>	
<p>Set basalt stone, 16 x 12 x 10 ins., 11 ins. in ground, for Cor. to Secs. 4, 5, 8 & 9, marked with 5 notches on S. and 4 notches on E. edges; from which</p>	
<p>A lodgepole pine, 8 ins. diam., brs. N.67°E., 27 lks. dist., marked T.2 S., R.35 E., S.4, B.T. (Old B.T.)</p>	
<p>A lodgepole pine, 8 ins. diam., brs. S.69°E., 28 lks. dist., marked T.2 S., R.35 E., S.9, B.T. (Old B.T.)</p>	
<p>A fir, 20 ins. diam., brs. S.21°30'W., 153 lks. dist., marked T.2 S., R.35 E., S.8, B.T. (New B.T.)</p>	
<p>A lodgepole pine, 10 ins. diam., brs. N.73°W., 58 lks. dist., marked T.2 S., R.35 E., S.5, B.T. (New B.T.)</p>	
<p>I mark a cross (X) on basalt stone, 4 x 4 x 2 ft., above ground, 30 lks. W. of Cor.</p>	
<p>Thence N., retracing line bet. Secs. 4 & 5.</p>	
<p>Over rolling bench land, through heavy timber & medium undergrowth.</p>	
36.75	<p>Leave brush, brs. N.W. & S.E.; descend 100 ft. to</p>
40.00	<p>Intersect the old $\frac{1}{4}$ Sec. Cor., which is an old post, badly decayed, marked & witnessed as described by the Surveyor-General, except that the N.E. bearing tree is now dead and fallen. I perpetuate this Cor., as follows; at the exact Cor. point</p>
<p>Set a red basalt stone, 15 x 15 x 10 ins., 10 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{2}$ 5 on W. & 4 on E. faces, from which</p>	
<p>A tamarack, 7 ins. diam., brs. S.82°W., 13 lks. dist., marked $\frac{1}{4}$ S.5, B.T. (Old B.T.)</p>	