

Exterior Lines, T. 3 N., R.27 E., W. M.

Chains		Feet
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 3, 4, 33 & 34, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Soil; heavy sand, 3rd rate.	
	Land; level. Considerable quantity of prickly pear.	
Subdivisional Lines, T. 3 N., R.27 E., W. M. As surveyed by Same Surveyor, under Same Contract & Date.		
	From the Cot. to Secs. 1, 2, 35 & 36, on S. Bdy. of T. 3 N., R.27 E., I run	
	N. bet. Secs. 35 & 36.	
7.00	The trail up Butter Creek brs. S.-S.W. Ascend hill brs. N. E. & S.W.	
34.00	Top of hill, 150 ft. high & descend.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; Deposited 1 pt. charcoal, as per instructions.	
66.50	Enter rolling ground.	
67.00	Road from Dalles to Walla Walla, brs. N.E.	
80.00	Set post for Cor. to Secs. 25, 26, 35 & 36, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Soil; 2nd & 3rd rate, producing grass.	
	Land; hilly.	
	E. on random line bet. Secs. 25 & 36.	
	Var. 19°20'E.	
40.00	Set temp. $\frac{1}{4}$ Secs. Cor.	
79.70	Intersect N. & S. line , 21 lks. S. of Cor. to Secs. 25, 36, 30 & 31, from which Cor., I run	
	S. 89°51'W. on true line bet. Secs. 25 & 36.	
22.40	Enter thick willow undergrowth.	
35.00	Leave willow undergrowth, which brs. N.-N.E.	
36.60	Butter Creek, 20 lks. wide, brs. N.-N.E.	
39.95	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits &	