

Subdivisional Lines, T.3 N., R.27 E., W. M.

Chains		Feet
	E. on random line bet. Secs. 26 & 35. Var. 19°15'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.96	Intersect N. & S. line, 22 lks. S. of Cor. to Secs. 25, 26, 35 & 36, from which Cor., I run S.89°51'W. on true line bet. Secs. 26 & 35.	
39.98	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
79.96	The Cor. to Secs. 34, 35, 26 & 27. Soil; 2nd rate. Land; high & rolling.	
	N. bet. Secs. 26 & 27.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 26, 27, 22 & 23, in mound, with trench & pits; deposited 1 pt. charcoal, as per instruc- tions.	
	E. on random line bet. Secs. 23 & 26. Var. 19°45' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.79	Intersect N. & S. line, 50 lks. S. of Cor. to Secs. 23, 24, 25 & 26, from which Cor., I run S.89°39'W. on true line bet. Secs. 23 & 26. Ascend irregular broken hill.	
39.89 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
44.00	Top of hill, 150 ft. high; enter rolling land	
79.79	The Cor. to Secs. 26, 27, 22 & 23. Land; hilly. Soil; 2nd & 3rd rate.	
	N. bet. Secs. 22 & 23.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	