

Subdivisional Lines, T.3 N., R.27 E., W. M.

Chains		Feet
	Land; rolling. Soil; 3rd rate.	
	<hr/>	
	N. bet. Secs. 10 & 11.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post, for Cor. to Secs. 10, 11, 2 & 3, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Soil; sandy 3rd rate. Land; broken & rolling.	
	<hr/>	
	E. on random line bet. Secs. 2 & 11.	
	Var. 19°48'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.70	Intersect N. & S. line, 18 lks. S. of Cor. to Secs. 1, 2, 11 & 12, from which Cor., I run	
	S.89°52'W. on true line bet. Secs. 2 & 11.	
39.85	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
79.70	The Cor. to Secs. 10, 11, 2 & 3. Soil; sandy & barren, some grass & prickly pear. Land; level.	
	<hr/>	
	N. on random line bet. Secs. 2 & 3.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.14	Intersect N. Bdy. of Tp., 33 lks. W. of Cor. to Secs. 2, 3, 10 & 11, from which Cor., I run	
	S.0°14'W. on true line bet. Secs. 2 & 3.	
40.14	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.14	The Cor. to Secs. 2, 3, 10 & 11. Soil; sandy, sterile, producing prickly pear. Land; level.	
	Oct. 13, 1860.	