

Exteriors and Subdivisions of T. 3, N. R. 28 E.
 Survey by N. H. Gates, under Contract No. 84.
 Dated July 22, 1859.

Chains

From the established corner to Townships 2 & 3, North of
 Ranges 27 and 28 East, I run North between Sections 31
 and 36.

- 10.00 Enter Butter Creek bottom; course N. E. and S.W.
 40.00 Set $\frac{1}{4}$ Sec. post in earth mound &c., as per instructions.
 80.00 Set post for corner to Secs. 30, 31, 25 & 36 in earth
 mound &c., as per instructions.

Land, level.

Soil, 1st & 2nd rate.

North between Secs. 25 & 30.

Variation 20° 15' East.

- 40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per
 instructions.

McRice's house bears S. 80° W. about 30 chains dist.

- 55.50 Road to upper crossing of Butter Creek, Course W. & E.
 60.00 Butter Creek, 15 links wide, course N. 45° E.
 62.75 Butter Creek, course N. 10° West.
 64.75 Leave same creek, course N.E.
 68.50 "Emmigrant Road" to Dalles. Course East and West.
 80.00 Set post for corner to Secs. 24, 25, 19 & 30 in mound
 of earth, as per instructions.

Land, level.

Soil, first rate.

North between Sections 19 & 24.

Variation 19° 50' East.

- 25.00 Leave Butter Creek bottom. Course N.E. and S.W.
 40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per
 instructions.
 80.00 Set post for corner to Secs. 18, 19, 13 & 24 in mound of
 earth with charred stake &c., as per instructions.

Land, gently rolling.

Soil, good 2nd rate.