

Subdivisions, T. 2, N., R. 28 E.

Chains	
79.38	Intersect N & S line 78 links South of sec. corner. S. 89° 27' W. on true line between Secs. 23 & 26.
39.69	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
53.20	Trail bears N & E.
79.38	The corner to Secs. 22, 23, 26 & 27 in mound of earth. Land, level. Soil, 2nd rate, sandy.
<hr/>	
	North between Secs. 22 & 23. Variation 20° East.
28.25	Emigrant Road bears E & W.
38.50	Emigrant Road to Umatilla River.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner 14, 15, 22 & 23 in mound of earth &c., as per instructions.
<hr/>	
	East on random line between Secs. 14 & 23.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
79.84	Intersect N & S Line 100 links South of Sec. corner. S. 89° 17' W. on true line between Secs. 14 & 23.
30.92	Road to Umatilla River from Emigrant Road bears N.E. & S.W.
39.92	Set post for $\frac{1}{4}$ Sec. corner in mound of earth, as per instructions.
79.84	The corner to Secs. 14, 15, 22 & 23. Land, level. Soil, 2nd rate.
<hr/>	
	North between Secs. 14 & 15. Variation 20° East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 10, 11, 14 & 15 in mound of