

## Subdivisions T. 3, N. R. 28 E.

Chains	
	North on random line between Secs. 2 & 3. Variation 20° East.
40.00	Set post for temp. 1/4 Sec. corner.
82.12	Intersect North boundary at Sec. corner.
	South on Line between Secs. 2 & 3.
42.12	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
82.17	The corner to Secs. 2, 3, 10 & 11. Land, level. Soil, 2nd rate, sandy.
<hr/>	
	North between Secs. 33 & 34.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 27, 28, 33 & 34 in mound of earth &c., as per instructions. Land, gently rolling. Soil, 2nd rate, sandy.
<hr/>	
	East on random line between Secs. 27 & 34.
40.00	Set post for temp. 1/4 Sec. corner.
80.05	Intersect N & S Line 70 links North of Sec. corner. N. 89° 30' W. on true line between Secs. 27 & 34.
40.93	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.05	The corner to Secs. 27, 28, 33 & 34 in mound of earth. Land, level. Soil, 1st rate.
<hr/>	
	North between Secs. 27 & 28. Variation 19° 50' East.
40.00	Set post for 1/4 Sec. corner in mound of earth, as per instructions.
80.00	Set post for corner to Secs. 21, 22, 27 & 28 in mound of earth, as per instructions.