

Chains	
80.00	earth, &c., as per instructions. Set post for corner to Secs. 20, 21, 28 & 29 in mound of earth, as per instructions. Land, gently rolling. Soil, 1st rate.
40.00	East on random line between Secs. 21 & 28. Set post for temp. 1/4 Sec. corner.
79.48	Intersect N & S Line 13 links North of Sec. corner. N. 89° 54' West on true Line between Secs. 21 & 28.
39.74	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.48	The corner to Secs. 20, 21, 28 & 29. Land, level. Soil, 1st rate. Sept. 25th, 1859.
13.25	North between Secs. 20 & 21. Variation 19° 15" East. Road bears N. 70° W. S 70° E.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
46.00	Emigrant Road from Missouri to Dalles bears East & West.
80.00	Set post for corner to Secs. 16, 17, 20 & 21 in mound of earth &c., as per instructions. Land, level. Soil, 1st rate.
40.00	East on random line between Secs. 16 & 21. Set post for temp. 1/4 Sec. corner.
79.36	Intersect N & S Line 24 links South of Sec. corner. S. 89° 50' W. on true line between Secs. 16 & 21.
39.68	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.36	The corner to Secs. 16, 17, 20 & 21 in mound of earth.