

Subdivisions T. 3, N. R. 28 E.

Chains	
	West on random line between Secs. 30 & 31.
40.00	Set post for temp. 1/4 Sec. corner.
78.70	Intersect West boundary 70 links South of corner. S. 89° 30' East on true line between Secs. 30 & 31.
32.70	Leave Butter Creek bottom, bears N & S.
38.70	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
78.70	The corner to Secs. 29, 30, 31 & 32. Land, level. Soil, 1st rate.
<hr/>	
	North between Secs. 29 & 30. Variation 20° East.
16.50	Road bears N.E. & S.W.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instruction.
80.00	Set post for corner to Secs. 19, 20, 29 & 30, in mound of earth &c., as per instructions. Land, level. Soil, 1st rate.
<hr/>	
	East on random line between Secs. 20 & 29. Variation 19° 45' East.
40.00	Set temp. 1/4 Sec. corner.
80.70	Intersect N & S Line 40 links North of Sec. corner. N. 89° 43' W. on true line between Secs. 20 & 29.
27.50	Road bears N.E. & S.W.
40.35	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.70	The corner to Secs. 19, 20, 29 & 30 in mound of earth. Land, level. Soil, 1st rate and sandy.
<hr/>	
	West on random line between Secs. 19 & 30.
40.00	Set post for temp. 1/4 Sec. corner.