

Subdivisions , T. 3, N. R. 28. E.

Chains	
77.50	Intersect West boundary 60 links South of corner. S.89° 44' E. on true line between Secs. 18 & 19.
20.00	Enter Bottom bears North & South.
37.60	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
51.00	Butter Creek 20 links wide, runs North.
77.60	The corner to Secs. 17, 18, 19 & 20, in mound of earth. Land, level. Soil, 1st rate.
	North between Secs. 17 & 18. Variation 20° 20' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
44.75	Butter Creek 20 links wide runs NE.
80.00	Set post for corner to Secs. 7, 8, 17 & 18 in mound of earth &c., as per instructions. Land, level. Soil, 1st rate.
	East on random line between Secs. 8 & 17.
40.00	Set post for temp. 1/4 Sec. corner.
80.16	Intersect N. & S. Line 80 links North of Sec. corner. N.89° 26' W. on true line between Secs. 8 & 17.
40.08	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
43.00	Leave Bottom, course N.E. & S.W.
48.00	Butter Creek runs N. 20° E. 20 links wide.
80.16	The corner to Secs. 7, 8, 17 & 18. Land, level. Soil, 1st rate.
	West on random line between Secs. 7 & 18.
40.00	Set post for temp. 1/4 Sec. corner.
77.23	Intersect West boundary at Sec. corner. East on true line between Secs. 7 & 18.