

Chains	30, East. The correction will, therefore, be 6.36 chains East and 42 links South per mile, and the true course of line S. 89° 42' W.
	S. 89° 42' W. on true line between Sections 1 and 36. Variation 20° 15' East.
40.00	Set post for 1/4 Section corner in mound of earth, established as per instructions.
80.00	Set post for corner to Sections 1 and 2, 35 & 36 in mound of earth, established as per instructions.
	Land, gently rolling. Soil, 2nd rate.
	S. 89° 42' W. on true line between Secs. 2 and 35. Variation 20° 20' East.
40.00	Set post for 1/4 Section corner, and established same in earth mound, as per instructions.
80.00	Set post for corner to Sections 2 and 3, 34 and 35, in earth mound, and established same as per instructions.
	Land, gently rolling. Soil, 2nd rate.
	S. 89° 42' W. on true line between Secs. 3 and 34. Variation 20° 35' East.
40.00	Set post for 1/4 Section corner in mound of earth, established as per instructions.
80.00	Set post for corner to Sections 3, 4, 33 & 34, in earth mound established as per instructions.
	Land, gently rolling. Soil, 2nd rate. September 13th, 1859.
	S. 89° 42' W. on true line between Secs. 4 and 33. Variation 21° East.
35.36	Trail, course, N.W. and S.E.