

Chains

and supplies in its bottoms plenty of timber for the purposes of the settler.

Field Notes of the Subdivision lines
in Tp. No. 3, North of Range 29 East.
Survey by N. H. Gates under his Contract
No. 84. Dated July 22, 1859.

North between Sections 35 & 36.

Descend hill.

36.00 Umatilla River 450 links wide, runs N. 70° W. Water shallow. No triangulation made.

41.00 Set post for witness to 1/4 Sec. corner in River, from which
a balm 5 in. diameter bears N. 47° W., 5 links dist.
a " 4 " " " N.30° E. 10 " "

Enter timber and bottom bears N.W. and S.E.

49.00 Leave timber, bears N.W. and S.E.

72.50 Emigrant Road bears N.W. and S.E.

77.00 Ascend hill. Leave bottom, bears N.W. and S.E.

80.00 Set post for corner to Secs. 25, 26, 35 and 36 in mound of earth &c., as per instructions.

Land, 1st and 2nd rate; that in bottom, first rate.

Timber on Umatilla River:

Birch, Cottonwood, Willow and Cherry, Crab Apple & Thorn.

East on random line between Sections 25 & 36.

40.00 Set post for temp. 1/4 Sec. corner.

79.47 Intersect East boundary 37 links South of Section corner.
S. 89° 44' W. on true line between Sections 25 & 36

39.74 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

79.47 The corner to Sections 25, 26, 35 & 36.

Land, hilly.

Soil, 2nd rate.

North between Secs. 25 & 26.

Variation 19½° East.