

Chains	
79.82	Intersect N. & S. line 21 links South of Sec. corner.
	S. 89° 51' W. on true line between Secs. 3 and 10.
39.91	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.82	The corner to Secs. 3, 4, 9 & 10 in mound of earth.
	Land, gently rolling.
	Soil, good 2nd rate.
<hr/> North between Secs. 3 & 4 on random line.	
	Variation 20° East.
40.00	Set post for temporary 1/4 Sec. corner.
80.94	Intersect North boundary 29 links East of Sec. corner.
	S. 0°12' East on true line between Secs. 3 & 4.
40.94	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.94	The corner to Secs. 3, 4, 9 and 10 in mound of earth.
	Land, level.
	Soil, good 2nd rate.
<hr/> North between Secs. 32 and 33.	
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 28, 29, 32 & 33 in mound of earth &c., as per instructions.
	Land, gently rolling.
	Soil, good 2nd rate.
<hr/> East on random line between Secs. 28 & 33.	
40.00	Set post for temporary 1/4 Sec. corner.
79.50	Intersect N. & S. line 70 links South of Sec. corner.
	S. 89° 30' W. on true line between Secs. 28 & 33.
39.75	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.50	The corner to Secs. 28, 29, 32 & 33.
	Land, gently rolling.
	Soil, good 2nd rate.