

N.Bdry., T. 3 N., R. 30 E.

Chains 80.00	<p>Set post for corner to Sections 3 and 4, 33 and 34 in earth mound established as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate.</p> <hr/> <p>West on true line between Secs. 4 and 33.</p> <p style="text-align: right;">Variation 20° 15' East</p>
40.00	<p>Set post for $\frac{1}{4}$ Section corner in earth mound, established as per instructions.</p>
80.00	<p>Set post for corner to Sections 4 and 5, 32 and 33, and established same in earth mound, as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate.</p> <hr/> <p>West on true line between Secs 5 and 32.</p> <p style="text-align: right;">Variation 19°40' East</p>
40.00	<p>Set post for $\frac{1}{4}$ Section corner in mound of earth established as per instructions.</p>
80.00	<p>Set post for corner to Sections 5 and 6, 31 and 32, in mound of earth established as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate.</p> <hr/> <p>West on true line between Secs. 6 and 31.</p> <p style="text-align: right;">Variation 20° 15' East</p>
40.00	<p>Set post for $\frac{1}{4}$ Section corner in earth mound established as per instructions.</p>
86.17	<p>Intersect the corner to Townships 3 and 4, North of Ranges 29 and 30 East.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p> <p style="text-align: right;">September 12th, 1859</p> <hr/> <p style="text-align: center;">General Description</p> <p>This Township, which is chiefly gently rolling prairie,</p>