

Subdivisions, T. 3 N., R 30 E.

Chains	
	West, on a true line between Secs. 13 & 24.
40.09	Set a post for quarter section corner, drove a charred stake and raised a mound of earth, with trench and pits, as per instructions.
80.18	The corner to Secs. 13, 14, 23 & 24. Soil, good 2nd rate. Land, level and rolling prairie.
	<hr/> North between Secs. 13 & 14.
40.00	Set a post for quarter section corner. Drove a charred stake and raised mound of earth, as per instructions.
80.00	Set a post for corner to Sections 11, 12, 13 & 14. Drove a charred stake and raised a mound of earth with trench and pits as per instructions. Land, nearly level. Prairie. Soil, good 2nd rate.
	<hr/> East on a random line between Secs. 12 & 13. Variation 9° 45' E.
40.00	Set a temporary quarter sec. post.
79.56	Intersect Guide Meridian 24 links South of post, corner secs. 12 & 13. S.89°50' W. On true line between Secs. 12 & 13.
39.78	Set a post for quarter section corner. Drove a charred stake and raised a mound of earth with trench & pits as per instructions.
79.56	The corner to sections 11, 12, 13 & 14. Land, rolling prairie. Soil, good, 2nd rate.
	<hr/> North between Secs. 11 & 12.
40.00	Set a post for quarter section corner, drove a charred stake and raised a mound of earth with trench and pits, as per instructions.
80.00	Set a post for corner to Secs. 1, 2, 11 & 12. Drove a