

Subdivisions, T. 3 N., R. 30 E.

Chains		
	charred stake and raised a mound of earth with trench and pits, as per instructions.	
80.00	Set a post for corner to Secs. 1, 2, 11 & 12, drove a charred stake and raised a mound of earth with trench and pits, as per instructions. Land, level prairie. Soil, good 2nd rate.	
<hr/>		
	East on a random line between sections 1 & 12. Variation 20° 15' E.	
40.00	Set a temporary quarter sec. corner post.	
79.55	Intersect Guide Meridian 30 links South of post corner to Secs. 1 & 12. S. 89° 47' W . on a true line between Secs. 1 & 12.	
39.78	Set a post for quarter section corner; drove a charred stake and raised a mound of earth with trench and pits as per instructions.	
79.55	The corner to Sections 1, 2, 11 & 12. Land, level, prairie. Soil, good 2nd rate.	
<hr/>		
	North on a random line between Secs. 1 & 2.	
40.00	Set a temporary post for qr. sec. corner.	
83.11	Intersect North boundary of Township, 50 links East of post corner to secs. 1 & 2. S.00° 21' E. on a true line between Secs. 1 & 2. Commence ascent.	-50
13.11	To top of ascent.	+50
43.11	Set a post for quarter section corner. Drove a charred stake and raised a mound of earth with trench and pits, as per instructions.	
83.11	The corner to Secs. 1, 2, 11 & 12. Land, gently rolling prairie. Soil, good 2nd rate.	
Oct. 18th, 1860.		