

Subdivisions, T. 3 N., R. 30 E.

Chains	
	North between Secs. 34 & 35. Commence to ascend bluff.
2.50	Top an Indian trail, course NW & SE
28.10	" Another " " " E. & W.
31.00	To a wagon road, " " " "
40.00	Set a quarter sec. post and drove a charred stake and raised a mound of earth with trench and pits, as per instructions.
45.00	To another Wagon road, branch of the above mentioned road, course N.W. & S.E., leading to lower Umatilla.
80.00	Set a post for corner to Secs. 26, 27, 34 & 35; drove a charred stake and raised a mound of earth with trench and pits, as per instructions.
	Land, gently rolling prairie. Soil, good 2nd rate.
<hr/>	
	East on a random line between Sections 26 & 35. Variation, 20° 30' E.
40.00	Set temporary quarter sec. post.
79.80	Intersect corner to Secs. 25, 26, 35 & 36, at post. West on a true line between Secs. 26 & 35.
39.90	Set a post for quarter section corner, drove a charred stake and raised mound of earth with trench and pits, as per instructions.
49.80	To trail, runs NW & SE.
79.80	The corner to Secs. 26, 27, 34 & 35. Land, gently rolling prairie. Soil, good 2nd rate.
<hr/>	
	North between Secs. 26 & 27.
40.00	Set post for quarter section corner, drove a charred stake and raised mound with trench and pits, as per instructions.
80.00	Set a post for corner to secs. 22, 23, 26 & 27. Drove a

†25