

Subdivisions of T. 3 N. R. 30 E.

| Chains | |
|--------|--|
| | <p>charred stake and raised mound with trench and pits, as per instructions.</p> <p>A snow peak in Cascade range bears N. 58° W.</p> <p>A " " " " " " N. 73° W., from this section post.</p> <p>Land, gently rolling prairie.</p> <p>Soil, good, 2nd rate.</p> |
| | <p>East on a random line between Secs. 25 & 26.</p> <p style="text-align: right;">Variation 20° 45' E.</p> |
| 40.00 | Set a temporary quarter sec. post. |
| 80.70 | Intersect N. & S. line at post corner to Secs. 23, 24, 25 & 26. |
| | West on a true line between Secs. 23 & 26. |
| 40.35 | Set a post for quarter section corner. Drove a charred stake and raised mound with trench and pits, as per instructions. |
| 80.40 | To a trail before noted, bears N.W. & S.E. |
| 80.70 | The corner to Secs. 22, 23, 26 & 27. |
| | <p>Land, gently rolling, nearly level prairie.</p> <p>Soil, good 2nd rate.</p> |
| | <p>North between Secs. 22 & 23.</p> |
| 2.50 | To Indian Trail before noted, course N.W. & S.E. |
| 40.00 | Set a post for quarter section corner. Drove a charred stake and raised mound with trench and pits, as per instructions. |
| 80.00 | Set a post for corner to secs. 14, 15, 22 & 23. Drove a charred stake and raised mound with trench and pits, as per instructions. |
| | <p>Land, gently rolling prairie, slightly descending to the North.</p> <p>Soil, good 2nd rate.</p> |
| | <p>East on random line between Secs. 14 & 23.</p> |