

Subdivisions, T. 3 N., R. 30 E.

Chains	
	Variation 20° 30' East.
40.00	Set a temporary quarter sec. post.
80.18	Intersect N & S line 16 links South of corner to Secs. 13, 14, 23 & 24. S.89° 53' W. on a true line between Secs. 14 & 23.
40.09	Set a post for quarter section corner. Drove charred stake and raised mound of earth with trench and pits, as per instructions.
80.18	The corner to Secs.14, 15, 22 & 23. Land, gently rolling prairie. Soil, good 2nd rate.
	North between Secs. 14 & 15.
40.00	Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
80.00	Set a post for corner to Secs. 10, 11, 14 & 15. Drove a charred stake and raised mound with trench and pits, as per instructions.
	East on a random line between Secs. 11 & 14. Variation 20° 30' E.
40.00	Set temporary quarter sec. post.
79.94	Intersect corner to Secs. 11, 12, 13 and 14 at post. West on a true line between Secs. 11 & 14.
39.97	Set a post for quarter section corner. Drove a charred stake and raised mound with trench & pits, as per instructions.
79.94	The corner to Secs. 10, 11, 14 & 15. Land, gently rolling prairie. Soil, good 2nd rate.
	North between Secs. 10 & 11.
40.00	Set a post for quarter section corner. Drove charred stake and raised mound of earth with trench and pits,