

Subdivisions, T. 3 N., R. 30 E.

Chains		
	East on random line between Secs. 22 & 27. Variation 21° E.	
40.00	Set temporary quarter Sec. post.	
79.74	Intersect corner to Secs. 22, 23, 26 & 27 at post. West on a true line between Secs. 22 & 27.	
39.87	Set a post for quarter section corner, drove charred stake &c., as per instructions.	
49.74	Commence descent into hollow, course W.	
54.74	Cross hollow and ascend.	-50
63.74	To top of bank.	+40
79.74	The post corner to Secs. 21, 22, 27 & 28. Land and soil same as last mile.	
<hr/>		
	North between Secs. 21 & 22.	
40.00	Set a post for quarter sec. corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.	
80.00	Set a post for corner to Secs. 15, 16, 21 & 22. Drove a charred stake and raised mound of earth, with trench and pits, as per instructions. Land, rolling prairie, slight descent to the North. Soil, good 2nd rate.	
<hr/>		
	East on a random line between Secs. 15 & 22. Variation 19° 30' E.	
40.00	Set a temporary quarter sec. post.	
79.74	Intersect N & S line 78 links North of corner to Secs. 14, 15, 22 & 23. N. 89° 27' W. on a true line between Secs. 15 & 22.	
7.54	To a trail, runs NW & SE.	
39.87	Set a post for quarter sec. corner and raised mound and drove charred stake &c., as per instructions.	
52.24	Commence descending rocky point.	
55.74	Cross hollow and commence ascending.	-40
61.24	To top of ascent.	+30