

Subdivisions, T.3 N., R. 30 E.

Chains		
	East on random line between Secs. 3 & 10. Variation 19° 35' E.	
40.00	Set a temporary quarter sec. post.	
80.46	Intersect corner to Secs. 2, 3, 10 & 11 at post. West on a true line between Secs. 3 & 10.	
40.23	Set a post for quarter sec. corner. Drove a charred stake and raised mound of earth, with trench and pits, as per instructions.	
42.46	To Indian Trail, before noted, course N & S.	
80.46	The corner to Secs. 3, 4, 9 & 10. Land, gently rolling prairie. Soil, good 2nd rate.	
<hr/>		
	North on a random line between Secs. 3 & 4.	
40.00	Set a temporary quarter section post.	
21.75	Intersect North boundary of Township, 31 links E. of post. Corner to Secs. 3 & 4. S. 00° 13' E. on a true line between Secs. 3 & 4.	
41.75	Set a post for quarter section corner, drove charred stake and raised mound of earth, with trench and pits, as per instructions.	
81.75	The corner to Secs. 3, 4, 9 & 10. Land, rolling prairie. Soil, good 2nd rate.	
<hr/>		
	North between Secs. 32 & 33. Ascend rocky bluff from post..	
5.00	To top of bluff, facing to the South.	4200
38.00	To a Wagon Road first noted from Dalles to Walla Walla. E & W.	
40.00	Set a post for quarter section corner, drove a charred stake and raised mound of earth with trench and pits, as per instructions.	level
74.00	To Indian Trail, course NW & SE	