

Subdivisions, T.3 N., R. 30 E.

Chains

80.00	Set a post for corner to Secs. 28, 29, 32 & 33. Drove a charred stake and raised mound of earth with trench and pits, as per instructions. Land on bluff, rocky, 3rd rate soil; balance, gently rolling prairie; soil, good 2nd rate.
	East on a random line between Secs. 28 & 33. Variation 21° 00' East
40.00	Set a temporary quarter section post.
80.40	Intersect corner to Secs. 27, 28, 33 & 34, at post. West on a true line between Secs. 28 & 33.
40.20	Set a post for quarter section corner, drove charred stake and raised mound with trench and pits, as per instructions.
80.40	The post corner to Secs. 28, 29, 32 & 33. Land, rolling, same as last mile.
	North between Secs. 28 & 29.
40.00	Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
52.00	Wagon road runs NW & SE.
80.00	Set a post for corner to Secs. 20, 21, 28 & 29. Drove a charred stake and raised mound with trench and pits, as per instructions. Land and soil, same as last mile.
	East on a random line between Secs. 21 & 28. Variation 20° 00' East
40.00	Set a temporary quarter sec. post.
79.80	Intersect corner to Secs. 21, 22, 27 & 28, at post. West on a true line between Secs. 21 & 28.
39.90	Set a post for quarter section corner, drove a charred stake and raised mound with trench and pits, as per instructions.