

## Subdivisions T. 3 N., R. 30 E.

Chains		
	Land, rolling prairie. Soil, good 2nd rate.	
	East on a random line between Secs. 9 & 16. Variation 20° 00' E.	
40.00	Set a temporary quarter section post.	
79.65	Intersect N & S line, 52 links North of corner to Secs. 9, 10, 15 & 16.	level
	N. 89° 38' W. on true line between Secs. 9 & 16.	
22.65	To hollow and ascend.	-25
39.83	Set a post for quarter section corner, drove a charred stake and raised mound of earth, with trench and pits, as per instructions.	
68.50	To Indian Trail, course NE & SW.	
79.66	The post corner to sections 8, 9, 16 & 17. Land, rolling prairie. Soil, good 2nd rate.	
	North between Secs. 8 & 9.	
40.00	Set a post for quarter section corner. Drove a charred stake and raised mound with trench and pits, as per instructions.	
80.00	Set a post for corner to Secs. 4, 5, 8 & 9. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.	level
	Land, rolling prairie. Soil, good 2nd rate.	
	October 22, 1860.	
	East on a random line between Secs. 4 & 9. Variation 21° 00' East	
40.00	Set temporary quarter sec. post.	
79.64	Intersect N & S line 42 links South of corner to Secs. 3, 4, 9 & 10.	level
	S. 89° 48' W. on a true line between Sections 4 & 9.	