

Subdivisions, T. 3 N., R. 30 E.

Chains	
	N.89° 38' W. on a true line between secs. 8 & 17.
39.80	Set a post for quarter section corner, drove a charred stake and raised a mound of earth, with trench and pits, as per instructions.
79.60	The post corner to secs. 7, 8, 17 and 18. Land, rolling prairie. Soil, good 2nd rate.
<hr/>	
	West on a random line between sections 7 & 18.
40.00	Set a temporary quarter sec. post.
89.50	Intersect West boundary of Township, 16 links North of corner to secs. 7 & 18. N. 89° 53' E. on a true line between Secs. 7 & 18.
49.50	Set a post for quarter section corner. Drove a charred stake and raised mound with trench and pits, as per instructions.
89.50	The post corner to sections 7, 8, 17 & 18. Land, gently rolling prairie. Soil, good 2nd rate.
<hr/>	
	North between sections 7 & 8.
40.00	Set post for quarter sec. corner. Drove charred stake and raised mound of earth, with trench and pits, as per instructions.
80.00	Set a post for corner to Secs. 5, 6, 7 & 8. Drove a charred stake and raised mound of earth, with trench and pits, as per instructions. Land, gently rolling. Soil, good 2nd rate.
<hr/>	
	East on a random line between Sections 5 & 8. Variation 20° 15' East.
40.00	Set temporary quarter section post.
79.70	Intersect N & S line 30 links North of corner to Secs. 4, 5, 8 & 9.