

Subdivisions T. 3 N., R. 30 E.

Chains		
39.85	N. 89° 47' W. on a true line between Sections 5 & 8. Set a post for quarter sec. corner. Drove charred stake and raised mound of earth with pits and trench, as per instructions.	0
79.70	The post corner to Sections 5, 6, 7 & 8. Land and soil same as last mile.	
<hr/> West on a random line between Sections 6 & 7.		
40.00	Set temporary quarter section post.	-50
89.78	Intersect West boundary of Township, 25 links South of post.	
49.78	S. 89° 49' E. on a true line between Secs. 6 & 7. Set a post for quarter section corner. Drove charred stake and raised mound of earth with trench and pits, as per instructions.	+25
89.78	The corner to Secs. 6 & 7. Land and soil the same as last mile.	+50
<hr/> North on a random line between Sections 5 & 6.		
40.00	Set a temporary quarter sec. post.	
81.09	Intersect North boundary of Township, 5 links East of post. Corner to Secs. 5 & 6.	+100
11.49	S. 00° 02' E. on a true line between Secs. 5 & 6. Commence descent from post.	
16.09	To foot of descent and to trail, running E & W.	-100
36.09	Commence ascending.	
41.09	To top of ascent. Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.	+100
81.09	The corner to Secs. 5 & 6, 7 & 8. Land, rolling prairie. Soil, 2nd rate.	
Oct. 26th, 1860.		