

East Boundary Township 3 N., R. 31 E.

Chains North on East line Section 13, T. 3 N., R. 31 E.
 40.00 Set charred stake with mound, trench and pits as per
 insts. for $\frac{1}{4}$ sec. corner

80.00 Dry Ravine (N. 80° W.)
 Set charred stake with mound, trench and pits as per
 insts. for corner to Secs. 12 & 13, R. 31 and 7 &
 18, R. 32, Town. 3 North.
 Var. 19°50' E.

Land, rolling.
 Soil, 2nd rate.

North on line between sections 12, R. 31 E. & 7, R. 32 E.
 T. 3 N.

40.00 Set charred stake with mound, trench and pits as per
 insts. for $\frac{1}{4}$ sec. corner.

80.00 Set charred stake with mound, trench and pits as per
 insts. for corner to Secs. 1 & 12, R. 31 and 6 & 7,
 R. 32.
 Var. 20° E.

North on line between sections 1, R. 31 & 6, R. 32.

40.00 Set charred stake with mound, trench and pits as per
 insts. for $\frac{1}{4}$ sec. corner.

56.50 Bottom of dry Ravine (West).

80.00 Set charred stake with mound, trench and pits as per
 insts. for corner to Townships 3 & 4 N., Ranges 31
 & 32 East.
 Var. 20°31' E.

Soil, 2nd rate

August 22. North Boundary

N. 89°18' W. on random North line of Town. 3 N., R. 31 E.

40.00 Set Temp. $\frac{1}{4}$ sec. post

80.00 Set Temp. post for corner to Sec. 1 & 2, T. 3 N., & Secs.
 35 & 36 T. 4 N.