

Subdivision Lines Township No. 3 N., R. 31 E., W.M.

| Chains | |
|---|---|
| 40.15 | Set charred stake with mound, trench and pits as per insts. for qr. Sec. corner. |
| 80.30 | Corner to Secs. 1 & 2, 11 & 12. Soil, 2nd rate. |
| North on random between Secs 1 & 2. | |
| 40.00 | Set Temp $\frac{1}{4}$ Sec. post. |
| 79.60 | Intersect North line Township No. 3 N. 15 links East of corner to Secs. 1 & 2. |
| S. 06' E. on true line between Secs 1 & 2. | |
| 39.60 | Set charred stake with mound, trench and pits as per instrs. for $\frac{1}{4}$ sec. corner. |
| 79.60 | Corner to Secs. 1 & 2, 11 & 12. Soil, sandy, rather poor. |
| North on line between Secs 34 & 35. | |
| Var. 19°50' E. | |
| 40.00 | Set charred stake with mound, trench and pits as per instrs. for qr. sec. corner. |
| 80.00 | Set charred stake with mound, trench and pits as per instrs. for corner to 26 & 27, 34 & 35. |
| Var. 20° 40' E. | |
| Surface, level. | |
| Soil, 1st rate. | |
| S. 89°18' E. on random between Secs. 26 & 35. | |
| 40.00 | Temp. $\frac{1}{4}$ sec. post. |
| 80.12 | Intersect line 26 lks. South of cor. to Secs. 25 & 26, 35 & 36 North 89°29' W. on true line between Secs. 26 & 35. |
| 40.06 | Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner. |
| 80.12 | Corner to Secs. 26, 27, 34 & 35. Soil, 1st rate. |
| North on line between Secs. 26 & 27. | |
| 40.00 | Set charred stake with mound, trench and pits as per insts. for qr. sec. corner. |