

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains

79.40 Corner to Secs. 2 & 3, 10 & 11.  
Same as last mile.

August 28

North on line between Secs. 33 & 34.

Var. 20° E.

40.00 Set charred stake with mound, trench and pits as per  
insts. for ¼ sec. corner.

80.00 Set charred stake with mound, trench and pits as per  
insts. for corner to Secs. 27 & 28, 33 & 34.

Var. 19°45' E.

Land, rolling.

Soil, 2nd rate.

S. 89°18' E. on random between Secs. 27 & 34.

40.00 Set Temp. ¼ sec. post.

80.00 Intersect section line 51 lks. South of corner to Secs.  
26 & 27, 34 & 35.

N. 89°40' W. on true line between Secs. 27 & 34.

40.00 Set charred stake with mound, trench and pits as per  
instructions for ¼ sec. corner.

80.00 Corner to Secs. 27, 28, 33 & 34.

North on line between Secs. 27 & 28.

40.00 Set charred stake with mound, trench and pits as per  
insts. for ¼ sec. corner.

80.00 Set charred stake with mound, trench and pits as per  
insts. for corner to sections 21, 22, 27 & 28.

Var. 19°33' E.

Soil, 2nd rate.

S. 89°18' E. on random between Secs. 22 & 27.

40.00 Set Temp. ¼ Sec. post.

80.00 Intersect sec. line 42 lks. South of post corner to  
Secs. 22, 23, 26 & 27.

N. 89°36' W. on true line between Secs. 22 & 27.