

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains	
13.00	Road to Walla Walla (E. & W.)
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 28 & 29, 32 & 33. Var. 20°20' E. Soil, good.
	S. 89°18' E. on random between Secs. 28 & 33.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
79.54	Intersect sec. line at post corner to Secs. 27 & 28, 33 & 34. N. 89°18' W. on true line between Secs. 28 & 33.
39.77	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
79.54	Corner to Secs. 28 & 29, 32 & 33. Soil, 2nd rate.
	North on line between Secs. 28 & 29.
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 20 & 21, 28 & 29. Var. 19°30' E. Soil, 2nd rate.
	S. 89°18' E. on random between Secs. 21 & 28.
40.00	Set Temp. $\frac{1}{4}$ post.
79.86	Int. sec. line 58 lks. North of corner to Secs. 21 & 22, 27 & 28. N. 89°54' W. on true line between Secs 21 & 28.
39.93	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
79.86	Corner to Secs. 20 & 21, 28 & 29. Land, level. Soil, 2nd rate.