

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains	
	20 & 21, 28 & 29.
	N. 89°51' W. on true line between Secs. 20 & 29.
39.95	Set charred stake with mound, trench & pits as per insts. for $\frac{1}{4}$ sec. corner.
79.90	Corner to Secs. 19 & 20, 29 & 30. Soil, 2nd rate.
	N. 89°18' W. on random between Secs. 19 & 30.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
82.60	Intersect Town. line 21 links North of corner to Secs. 19 & 30.
	S. 89°27' E. on true line between Secs. 19 & 30.
42.60	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
82.60	Corner to Secs. 19, 20, 29 & 30. Soil, 2nd rate.
	North on line between Secs. 19 & 20.
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 17 & 18, 19 & 20.
	Var. 19°20' E.
	Soil, good.
	S. 89°18' E. on random between Secs. 17 & 20.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
79.72	Intersect Sec. line 70 links South of corner to sections 16, 17, 20, & 21.
	N. 89°48' E. on true line between Secs. 17 & 20.
39.86	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
79.72	Corner to Sec. 17, 18, 19 & 20. Soil, 2nd rate.
	N. 89°18' W. on random between Secs. 18 & 19.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
82.80	Intersect Town. line 28 links North of corner to Secs.