

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains	18 & 19.
	S. 89°30' E. on true line between Secs 18 & 19.
42.80	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
82.80	Corner to Secs. 17, 18, 19 & 20.
<hr/>	
	August 31
	North on line between Secs 17 & 18.
40.00	Set charred stake with mound, trench & pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 7, 8, 17 & 18. Var. 20° E.
	Soil, 2nd rate.
<hr/>	
	S. 89°18' E. on random between Secs. 8 & 17.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
79.60	Intersect Sec. line 29 links South of corner to Secs. 8, 9, 16 & 17.
	N. 89°30' W. on true line between Secs. 8 & 17.
39.80	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
45.00	Ravine N. 45° W.
79.60	Corner to Secs. 7, 8, 17 & 18. Soil, 2nd rate
<hr/>	
	N. 89°18' W. on random between Secs. 7 & 18.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
82.32	Intersect Town. line 25 links North of corner to Secs. 7 & 18.
	S. 89°28' E. on true line between Secs. 7 & 18.
42.32	Set charred stake with mound, trench & pits as per insts. for $\frac{1}{4}$ sec. corner.
82.32	Corner to Secs. 7, 8, 17 & 18. Soil sandy, 2nd rate.
<hr/>	
	North on line between Secs 7 & 8.
24.00	Ravine N. 45° W.