

Survey of the Exterior boundaries of Township No. 3 North of Range No. 32 East of the Willamette Meridian in the State of Oregon by David P. Thompson, deputy Surveyor, under his Contract, No. 106, bearing date the 16th day of August, 1864.

East Boundary

Chains	Commenced September 14th 1864 Completed September 15th 1864
	North on East boundary of Sec. 36.
	Var. 16°15' East
40.00	Set post for ¼ Sec. corner in mound of Earth with charred stake, pits, trench &c as per instructions.
	Var. 20°30' East
80.00	Set post for corner to Secs. 30, 31, 25 & 36 in mound of Earth with charred stake, pits, trench &c as per instructions.
	Land, gently rolling Soil, good 2nd rate.
	North on East boundary of Sec. 25.
	Var. 20° East.
40.00	Set post for ¼ Sec. corner in mound of Earth with charred stake, pits, trench &c as per instructions.
80.00	Set post for corner to Secs. 24, 25, 19 & 30 in mound of Earth with charred stake, pits, trench, &c as per instructions.
	Land, gently rolling. Soil, good 2nd rate.
	North on East boundary of Sec 24.
	Var. 20° East.
40.00	Set Stone 18x10x6 in. for ¼ Sec. corner.
63.85	Umatilla & Walla Walla Road bears N. E. & S. W.
80.00	Set post for corner to Secs. 18, 19, 13 & 24. in mound of Earth with charred stake, pits, trench &c as per instructions.
	Land level. Soil good 2nd rate. September 14th 1864.
	North on East boundary of Sec. 13.
	Var. 21° East.
40.00	Set post for ¼ Sec. corner in mound of Earth with charred stake, pits, trench, &c as per instructions.