

Survey of the Subdivisions of Township 3 North of the
Baseline of Range 32 East of the Willamette Meridian,
by Daniel Chaplin, deputy Surveyor under his contract,
No. 107, bearing date the 21st day of September 1864

Chains	
	Commenced October 25th 1864 Completed October 30th 1864
	North between Secs. 35 & 36
40.00	Set Stone 14x8x6 for $\frac{1}{4}$ Sec. cor.
80.00	Set post for corner to Secs. 25, 26, 35 & 36 in mound of Earth with charred stake, pits, &c as per instructions. Land, gently rolling. Soil, good 2nd rate.
	East on a random line between Secs. 25 & 36.
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersect East boundary 20 lks. South of corner to Secs. 25 & 36 from which I run S. 89°51' W. on a true line between Secs. 25 & 36.
40.00	Set Stone 15x14x6 for $\frac{1}{4}$ Sec. cor.
80.00	The corner to Secs. 25, 26, 35 & 36. Land, gently rolling. Soil, 2nd rate.
	North between Secs. 25 & 26.
	Var. 20° E.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
77.25	Umatilla & Walla Walla Road bears S.W. & N.E.
80.00	Set post for corner to Secs. 23, 24, 25 & 26 in mound of Earth with charred stake, pits &c as per instructions. Land, level. Soil, good 2nd rate.
	East on a random line between Secs. 24 & 25.
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.20	Intersect East boundary 24 lks. South of corner to Secs. 24 & 25 from which corner I run S. 89°50' W. on a true line between Secs. 24 & 25.
40.10	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.