

Subdivision Lines of Township 3 North, Range 32 E., W.M.

Chains

North on a random line between Secs. 2 & 3.

Var. 20° E.

40.00 Set post for temporary 1/4 Sec. corner.

80.60 Intersect north boundary 30 lks. West of corner to Secs. 2 & 3 from which I run S. 0° 13' W. on a true line between Secs. 2 & 3.

40.60 Set post for 1/4 Sec. corner in mound of Earth with charred stake, pits &c as per instructions.

80.60 The corner to Secs. 2, 3, 10 & 11.

Land, gently rolling.

Soil, good 2nd rate.

October 26th 1864

North between Secs. 33 & 34.

40.00 Set Stone 18x12x4 for 1/4 Sec. cor.

80.00 Set post for corner to Secs 33 & 34, 27 & 28 in mound of Earth with charred stake, pits &c as per instructions.

Land, level grass plain.

Soil, good 2nd rate.

East on a random line between Secs. 27 & 34.

40.00 Set post for temporary 1/4 Sec. cor.

80.75 Intersect N. & S. line 27 lks. North of corner to Secs. 26, 27, 34 & 35 from which I run N. 89°48' W. on a true line between Secs. 27 & 34.

40.37 Set post for 1/4 Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.

80.75 The corner to Secs. 27, 28, 33 & 34.

Land, level grass plains.

Soil, good 2nd rate.

North between Secs. 27 & 28.

Var. 20° E.

40.00 Set post for 1/4 Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.

80.00 Set post for corner to Secs. 21, 22, 27 & 28 in