

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	
80.00	Set post for corner to Secs. 17, 18, 19 & 20 in mound of Earth with charred stake, pits &c as per instructions. Land, level. Soil, 2nd rate.
East on a random line between Secs. 17 & 20.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.66	Intersect N. & S. line 13 lks. South of corner to Secs. 16, 17, 20 & 21 from which I run S. 89°54' W. on a true line between Secs. 17 & 20.
40.33	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.66	The corner to Secs. 17, 18, 19 & 20. Land, level. Soil, 2nd rate.
West on a random line between Secs. 18 & 19.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
84.56	Intersect West boundary 60 lks. South of corner to Secs. 18 & 19 from which I run S. 89°34' E. on a true line between Secs. 18 & 19.
44.56	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
84.56	The corner to Secs. 17, 18, 19 & 20. Land, level. Soil, 2nd rate.
North between Secs. 17 & 18.	
Var. 20° E.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
60.80	Ravine bears West.
80.00	Set post for corner to Secs. 7, 8, 17 & 18 in mound of Earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, 2nd rate.