

Survey of the exterior boundaries of Township No. 3 North of the baseline of Range 33, East of the Willamette Meridian in the State of Oregon by David P. Thompson, deputy Surveyor, under his Contract No. 106, bearing date, the 16th day of August 1864.

Chains	<p>Commenced Sept. 22nd 1864. Completed October 1st 1864.</p> <p>North on East boundary of Sec. 36.</p> <p style="text-align: right;">Var. 20°30' East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>77.00 Indian trail bears NE. & SW.</p> <p>80.00 Set post for corner to Secs. 30, 31, 25 & 36 in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>Land, level. Soil, 1st rate.</p>
	<p>North on East boundary of Sec. 25.</p> <p style="text-align: right;">Variation 21° East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>80.00 Set post for corner to Secs. 24, 25, 19 & 30 in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>Land, level. Soil, 1st rate</p>
	<p>North on East boundary of Sec. 24.</p> <p style="text-align: right;">Variation 20°45' East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>80.00 Set post for corner to Secs. 18, 19, 13 & 24 in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>Land, level. Soil, 1st rate. Sept. 22, 1864 Note The weather is now very cloudy, so I can do nothing. And the variation of the needle is very changeable.</p>
	<p>North on East boundary of Sec. 13.</p> <p style="text-align: right;">Variation 20°30' East.</p> <p>15.00 Dry bed of Creek runs SW.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.</p>