

North Boundary of Township 3 North, Range 33 E. W. M.

Chains	<p>East on North boundary of Sec. 2.</p> <p style="text-align: right;">Variation 20° East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>80.00 Set post for corner to Secs. 1, 2, 35 & 36 in mound of earth with charred stake, pits, trench &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, 1st rate.</p>
	<p>East on North boundary of Sec. 1.</p> <p style="text-align: right;">Variation 21° East.</p> <p>40.00 Set stone 17x10x5 ins. for $\frac{1}{4}$ Sec. corner.</p> <p>71.00 Umatilla and Walla Walla road bears NE. & SW.</p> <p>80.00 The corner to Townships 3 & 4 North, Ranges 33 & 34 East.</p> <p style="text-align: right;">Variation 20°30' East.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate. October 1st 1864.</p>
	<p>General Description</p> <p>The quality of land in this Township is good, being generally level or gently rolling and is well watered by numerous springs through various portions of the Township.</p> <p>There is however, no timber.</p> <p>There are a number of settlers and it should be subdivided.</p>
	<p>Survey of Township No. 3 North, Range No. 33 East, Willamette Meridian in the State of Oregon by Daniel Chaplin, deputy Surveyor, executed under his contract, No. 107, bearing date, the 21st day of September 1864.</p> <p>Commenced November 5th 1864 Completed November 11th 1864.</p> <p>North between Secs. 35 & 36.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.</p> <p>80.00 Set post for corner to Secs. 25, 26, 35 & 36 in mound of earth with charred stake, pits &c as per instructions.</p> <p>Land level.</p>