

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains	Soil, 1st rate.
	East on a random line between Secs. 25 & 36.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
79.50	Intersect East boundary 48 lks. North of corner to Secs. 25 & 36 from which I run
	N. 89°39' W. on a true line between Secs. 25 & 36.
39.75	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
79.50	The corner to Secs. 25, 26, 35 & 36.
	Land, level.
	Soil, 1st rate.
	North between Secs. 25 & 26.
	Var. 20° E.
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 23, 24, 25 & 26 in mound of earth with charred stake, pits &c as per instructions.
	Land, level.
	Soil, 1st rate.
	East on a random line between Secs. 24 & 25.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
79.32	Intersect East boundary 72 lks. North of corner to secs. 24 & 25 from which I run.
	N. 89°29' W. on a true line between Secs. 24 & 25.
39.66	Set post for $\frac{1}{4}$ sec. corner mound of earth with charred stake, pits &c as per instructions.
79.32	The corner to secs. 23, 24, 25 & 26.
	Land, level.
	Soil, 1st rate.
	North between Secs. 23 & 24.
	Var. 18° E.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
64.40	Dry bed of creek runs SW.