

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains	
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 1, 2, 11 & 12 in mound of earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, good 2nd rate.
	East on a random line between Secs. 1 & 12.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.00	Intersect East boundary 30 lks. North of corner to Secs. 1 & 12 from which corner I run N. 89°47' W. on a true line between Secs. 1 & 12.
39.50	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
79.00	The corner to Secs. 1, 2, 11 & 12. Land, gently rolling. Soil, 2nd rate.
	North on a random line between Secs. 1 & 2. Var. 21 $\frac{1}{2}$ ° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.80	Intersect North boundary 94 lks. East of corner to Secs. 1 & 2 from which I run S. 0°40' E. on a true line between Secs. 1 & 2
26.30	Umatilla Road bears NE. & SW.
39.80	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
79.80	The corner to Secs. 1, 2, 11 & 12 Land, level. Soil, 1st rate.
	North between Secs. 34 & 35.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 34, 35, 26 & 27 in mound of earth with charred stake, pits &c as per instructions. Land, level.