

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains	North between Secs. 22 & 23. Var. 20° E.
25.80	Dry bed of creek, course SW.
40.00	Set stone 22x8x5 for $\frac{1}{4}$ sec. cor.
80.00	Set post for corner to Secs. 14, 15, 22 & 23 in mound of earth with charred stake, pits &c as per instructions. Land, rolling. Soil, good 2nd rate.
	East on a random line between Secs. 14 & 23.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. & S. line 44 lks. North of corner to Secs. 13, 14, 23 & 24 from which corner I run N. 89°41' W. on a true line between Secs. 14 & 23.
40.00	Set stone 16x12x4 for $\frac{1}{4}$ sec. corner.
80.00	The corner to Secs. 14, 15, 22 & 23. Land, rolling. Soil, good 2nd rate.
	North between Secs. 14 & 15. Var. 20° E.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 10, 11, 14 & 15 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
	East on random line between Secs. 11 & 14.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.21	Intersect N. & S. line 35 lks. North of corner to Secs. 11, 12, 13 & 14 from which corner I run N. 89°45' W. on a true line between Secs. 11 & 14
40.10	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.21	The corner to Secs. 10, 11, 14 & 15. Land, level.