

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains	stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 33, 34, 27 & 28 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
	East on a random line between Secs. 27 & 34.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. & S. line 36 lks. South of corner to Secs. 26, 27, 34 & 35 from which corner I run S. 89°45' W. on a true line between Secs. 27 & 34.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	The corner to Secs. 33, 34, 27 & 28. Land, level. Soil, 1st rate. November 6th 1864
	North between Secs. 27 & 28. Var. 20° East.
40.00	Set stone 15x10x5 for $\frac{1}{4}$ sec. cor.
80.00	Set post for corner to Secs. 21, 22, 27 & 28 in mound of earth with charred stake, pits &c as per instructions. Land, rolling. Soil, 1st rate.
	East on a random line between Secs. 22 & 27.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
80.10	Intersect N. & S. line 30 lks. South of corner to Secs. 22, 23, 26 & 27 from which corner I run S. 89°47' W. on a true line between Secs. 22 & 27.
40.05	Set stone 20x8x6 for $\frac{1}{4}$ sec. cor.
80.10	The corner to Secs. 21, 22, 27 & 28. Land, rolling. Soil, 1st rate.
	North between Secs. 21 & 22. Var. 20$\frac{1}{2}$° E.
15.50	Enter field, bears NE. & SW.
20.40	Dry bed of creek, course SW. Leave field.