

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains		
	Land, level. Soil, 1st rate.	
	East on a random line between Secs. 28 & 33.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
80.60	Intersect N. & S. line at corner to Secs. 27, 28, 33 & 34 from which corner I run	
	West on a true line between Secs. 28 & 33.	
40.30	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
80.60	The corner to Secs. 28, 29, 32 & 33.	
	Land, level. Soil, 1st rate.	
	North between Secs. 28 & 29. Var. $20\frac{1}{2}^{\circ}$ E.	
38.50	Dry bed of creek, course SW. Enter field, bears NE & SW.	
40.00	Set post in mound of earth with charred stake, pits &c as per instructions.	
56.33	Leave field, bears NE. & SW. Ascend hill.	
80.00	Set stone 20x10x10 for corner to Secs. 20, 21, 28 & 29.	+200
	Land, rolling. Soil, 1st rate.	
	East on a random line between Secs. 21 & 28.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
80.45	Intersect N. & S. line at corner to Secs. 21, 22, 27 & 28 from which I run	
	West on a true line between Secs. 21 & 28.	
17.00	Descend hill.	
24.00	Foot of hill. Enter field, bears NE. & SW. House bears N. 45° E. 7 chs. dist.	
36.50	Dry bed of creek, course SW. Leave field, bears NE. & SW. Ascend hill.	-150