

Subdivisions of Township 3 North, Range 33 East W.M.

Chains	<p>Land, level.</p> <p>Soil, 1st rate.</p>
	<p>North between Secs. 31 & 32.</p>
40.00	Set stone 17x12x8 for $\frac{1}{4}$ sec. corner.
57.50	Dry bed of creek, course SW.
65.00	Ascend hill.
80.00	Set post for corner to Secs. 29, 30, 31 & 32 in mound of earth with charred stake, pits &c as per instructions.
	<p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
	<p>East on a random line between Secs. 29 & 32.</p>
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.00	Intersect S. line 30 lks. North of corner to Secs. 28, 29, 32 & 33 from which I run
	N. 89°47' W. on a true line between Secs. 29 & 32.
	Descend hill.
40.00	Set stone 12x8x8 for $\frac{1}{4}$ sec. cor.
	Foot of hill.
	House bears S. 45° E. 15.00 chs. dist.
57.50	Dry bed of creek, course SW.
58.00	Ascend hill.
70.00	Top of hill.
80.00	The corner to Secs. 29, 30, 31 & 32.
	<p>Land, hilly.</p> <p>Soil, good 2nd rate.</p>
	<p>West on a random line between Secs. 30 & 31.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.49	Intersect West boundary at corner to Secs. 30 & 31 from which I run
	East on a true line between Secs. 30 & 31.
39.49	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
79.49	The corner to Secs. 29, 30, 31 & 32.
	Land, level.