

Subdivisions of Township 3 North, Range 33 East W. M.

Chains	Soil, 1st rate.	November 9th 1864
	North between Secs. 29 & 30.	
	Var. 19 $\frac{3}{4}$ ° E.	
29.50	Ravine bears East.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
80.00	Set stone 15x12x10 for corner to Secs. 19, 20, 29 & 30. Land, hilly.	
	Soil, 3rd rate.	
	East on a random line between Secs. 20 & 29.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
80.40	Intersect N. & S. line 37 lks. North of corner to Secs. 20, 21, 28 & 29 from which corner I run	
	N. 89°44' W. on a true line between Secs. 20 & 29.	
40.20	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
80.40	The corner to Secs. 19, 20, 29 & 30.	
	Land, level.	
	Soil, 2nd rate.	
	West on random line between Secs. 19 & 30.	
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.	
79.20	Intersect West boundary at corner to Secs. 19 & 30 from which I run	
	East on a true line between Secs. 19 & 30.	
39.20	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
79.20	The corner to Secs. 19, 20, 29 & 30.	
	Land, rolling.	
	Soil, good 2nd rate.	
	North between Secs. 19 & 20.	
	Var. 20° E.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	