

Subdivisions of Township 3 North, Range 33 East W. M.

Chains	East on a random line between Secs. 8 & 17.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
80.30	Intersect N. & S. line 30 lks. North of corner to Secs. 8, 9, 16 & 17 from which corner I run.
	N. 89°47' W. on a true line between Secs. 8 & 17.
40.15	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions
44.40	Walla Walla & Umatilla Road bears NE. & SW.
80.30	The corner to Secs. 7, 8, 17 & 18.
	Land, level.
	Soil, 2nd rate.
	West on a random line between Secs. 7 & 18.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
78.00	Intersect West boundary at corner to Secs. 7 & 18 from which I run
	East on a true line between Secs. 7 & 18.
38.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
78.00	The corner to Secs. 7, 8, 17 & 18.
	Land, level.
	Soil, 1st rate.
	North between Secs. 7 & 8.
	Var. 20° E.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 5, 6, 7 & 8 in mound of earth with charred stake, pits &c as per instructions.
	Land, level.
	Soil, 1st rate. November 10th 1864.
	East on a random line between Secs. 5 & 8.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.20	Intersect N. & S. line 34 lks. North of corner to Secs. 4, 5, 8 & 9 from which I run
	N 89°45' W. on a true line between Secs. 5 & 8.