

Subdivisions of Township 3 North, Range 33 East Willa-
 mette Meridian, surveyed by James P. Currin and James E.
 Noland, deputy surveyors under special joint contract,
 dated May 4th 1887.

Chains	Commencing at cor. to Secs. 13 & 24, 18 & 19 on Township line bet. T. 3 N., Rs. 33 & 34 E. I run West on random bet. Secs. 13 & 24. Va. $21\frac{1}{2}^{\circ}$ East.
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at
79.00	I intersect N. and S. line 75 lks. N. of cor. to Secs. 13, 14, 23 and 24 which is a stone 10x10x10 ins. buried in the ground, mkd. with 1 notch on E. and 3 notches on S. edges. Pits have been destroyed. N. $89^{\circ}28'$ E. on true line bet. Secs. 13 & 24. Va. $17\frac{3}{4}^{\circ}$ East.
23.50	O. R. and N. Railway, course SW.
24.70	E. bank of Wild Horse creek, course SW. and set basalt stone 18x14x8 ins. 12 ins in the ground for Meander cor. to fractional Secs. 13 & 24, mkd. U R M C with T 3 N on E., R 33 E S 13 on N., and S 24 on S. faces and dug a pit 3 ft. sq., 1 ft. deep, 8 lks. E. of stone and raised md. of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.
39.50	Set basalt stone 22x8x5 ins. 14 ins. in the ground for $\frac{1}{4}$ sec. cor., mkd. $\frac{1}{4}$ on N. face. Dug pits 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised md. of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
79.00	Land, rolling. Soil, 1st rate; not cultivated. No timber. Poor grass.
South bet. Secs. 23 and 24. Va. $17\frac{3}{4}^{\circ}$ East	
14.10	O. R. and N. Railroad, course SW.
14.90	Set basalt stone 18x10x8 ins. 12 ins. in the ground for Meander corner to fractional Secs. 23 and 24, marked M. C. with T 3 N on S., S 24 R 33 E on E., and S 23 on W., and dug a pit 3 ft. square, 1 ft. deep, 8 lks. S. of stone, and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.
15.55	Wild Horse Creek, 5 lks. wide with course SW.