

Subdivisions of T. 3 North, R. 33 East

Chains 31.75	Wagon road, course NW.
40.00	Set post 3 ft. long, 3 ins. sq. 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S. on W. face; dug pits 18x18x-12 ins. N. and S. of post, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base around post.
80.00	Set post 4 ft. long, 4 ins. sq. 24 ins. in the ground for cor. to Secs. 23, 24, 25 & 26, marked T 3 N S 24 on NE., R 33 E S 25 on SE., S 26 on SW. and S 23 on NW. faces with 2 notches on S. and 1 notch on E. edges, and dug pits 18x18x12 ins. in each sec., 5 $\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base around post. Land, rolling. Soil, 2nd rate of a light ashy nature. Uncultivated. No timber. Poor grass.
	East on a random bet. Secs. 24 and 25. Va. 21° East.
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at
78.80	Intersect E. bdy., Township 75 lks. S. of cor. to Secs. 24, 25, 19 and 30. Thence S. 89°28' W. on true line. Va. 20 $\frac{1}{2}$ ° East.
39.40	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on N. face, dug pits 18x18x12 ins. E. and W. of post, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base around it.
53.00	Wagon road, course SW.
78.80	Cor. to Secs. 23, 24, 25 and 26. Land, slightly rolling. Soil, a kind of light, ashy nature, 2nd rate. Not cultivated. No timber. Poor grass.
	South bet. Secs. 25 and 26. Va. 20° East.
2.80	Wagon road, course SE.